FINISH SCHEDULE – AREA "A" FIRST FLOOR

RM. NO.	ROOM NAME	FLOOR: TERRAZZO	FLOOR: SEALED CONCRETE	FLOOR: QUARRY TILE	FLOOR: CERAMIC TILE	FLOOR: VINYL COMPOSITE TILE	FLOOR: CARPET	FLOOR: WOOD	BASE: TERRAZZO BASE	BASE: QUARRY TILE BASE	BASE: CERAMIC TILE BASE	BASE: 4" RUBBER BASE	WALL: GYP. BD.–PAINT	WALL: C.M.U. – PAINTED	WALL: C.M.U. – EPOXY FINISH	WALL: CERAMIC TILE	WALL: CURTAIN WALL	CEILING: ACOUST. LAY–IN TYPE A	CEILING: GYPSUM BD.–PAINT	CEILING: EXPOSED STRUCT.	CEILING: PTD. EXPOSED STRUCT.	CEILING HEIGHT	REMARKS
A100	CORRIDOR	●							●					●				●				13'–0"	–
A101	ART ROOM					●						●		●				●				13'–0"	–
A102	KILN					●						●		●				●				10'–0"	–
A103	CHAIR STORAGE					●						●		●				●				10'–0"	–
A104	RISER STORAGE					●						●		●				●				10'–0"	–
A105	INSTRUMENT STORAGE					●						●		●				●				10'–0"	–
A110	MUSIC I						●					●		●							●	–	APPX. 15' TO UNDERSIDE OF STRUCT.
A107	OFFICE						●					●		●				●				10'–0"	–
A108	MUSIC STORAGE					●						●		●				●				10'–0"	–
A109	PRACTICE ROOM						●					●		●				●				10'–0"	–
A110	MUSIC ROOM II						●					●		●							●	–	APPX. 15' TO UNDERSIDE OF STRUCT.
A111	PRACTICE ROOM						●					●		●				●				10'–0"	–
A112	PRACTICE ROOM						●					●		●				●				10'–0"	–
A113	OFFICE						●					●		●				●				10'–0"	–
A114	RAMP					●						●		●				●				VARIES	–
A118	STAGE					●		●				●		●							●	–	FLOOR AT FORESTAGE – WOOD FLOOR AT BACKSTAGE – VINYL (BLACK)
A117	CAFETERIA					●						●		●				●				13'–0"	–
A118	CUSTODIAL EQUIPMENT					●						●		●				●				10'–0"	–
A119	RECEIVING STORAGE					●						●		●				●				10'–0"	–
A120	CUSTODIAL SUPPLIES			●						●				●				●				10'–0"	–
A121	RECEIVING			●						●				●				●				12'–0"	–
A122	DRY STORAGE			●						●				●				●				10'–0"	–
A123	FREEZER	●																		●		–	–
A124	SERVING LINES			●						●				●				●				12'–0"	–
A125	DISHWASH			●						●				●				●				12'–0"	–
A126	KITCHEN			●						●				●				●				12'–0"	–
A127	COOLER	●																		●		–	–
A128	CHEMICAL STORAGE			●						●				●				●				10'–0"	–
A129	OFFICE			●						●				●				●				10'–0"	–
A130	COATS			●						●				●				●				10'–0"	–
C–1	CUSTODIAL			●										●						●		–	PROVIDE TA–8 AT MOP SINK, RE: SPECS
E–1	ELECTRICAL	●												●						●		–	–
M–1	MECHANICAL	●												●						●		–	–
RR–1	BOY'S RESTROOM				●						●					●		●				10'–0"	–
RR–2	GIRL'S RESTROOM				●						●					●		●				10'–0"	–
RR–3	WOMEN'S RESTROOM				●						●					●		●				10'–0"	–
RR–4	MEN'S RESTROOM				●						●					●		●				10'–0"	–
RR–5	TOILET			●						●						●		●				10'–0"	–
S–1	STAIR		●												●					●		–	–
S–2	STAIR		●												●					●		–	–

● MATERIAL AND FINISH APPLY TO ALL SURFACES

⊗ MATERIAL FINISH APPLIED ON SURFACE BY QUADRANT SHADED QUADRANT ORIENTATION SAME AS FLOOR PLAN

FINISH SCHEDULE – AREA "B" FIRST FLOOR

RM. NO.	ROOM NAME	FLOOR: TERRAZZO	FLOOR: SEALED CONCRETE	FLOOR: QUARRY TILE	FLOOR: CERAMIC TILE	FLOOR: VINYL COMPOSITE TILE	FLOOR: CARPET	BASE: TERRAZZO BASE	BASE: QUARRY TILE BASE	BASE: CERAMIC TILE BASE	BASE: 4" RUBBER BASE	WALL: GYP. BD.–PAINT	WALL: C.M.U. – PAINTED	WALL: CERAMIC TILE	CEILING: ACOUST. LAY–IN TYPE A	CEILING: GYPSUM BD.–PAINT	CEILING: EXPOSED STRUCT.	CEILING HEIGHT	REMARKS
B100	COMMONS	●						●					●			●		VARIES	–
B101	VESTIBULE	●						●					●			●		VARIES	–
B102	RECEPTION	●						●					●		●			10'–0"	–
B103	CONFERENCE ROOM					●				●			●		●			10'–0"	–
B104	PRINCIPAL'S OFFICE					●				●			●		●			10'–0"	–
B105	OFFICE					●				●			●		●			10'–0"	–
B106	COUNSELOR					●				●			●		●			10'–0"	–
B107	COUNSELOR					●				●			●		●			10'–0"	–
B108	SMALL CONFERENCE ROOM					●				●			●		●			10'–0"	–
B109	CORRIDOR					●				●			●		●			10'–0"	–
B111	STORAGE					●				●			●		●			10'–0"	–
B112	BOOK KEEPER					●				●			●		●			10'–0"	–
B113	RECORDS					●				●			●		●			10'–0"	–
B114	DATA					●				●			●		●			10'–0"	–
B115	OFFICE					●				●			●		●			10'–0"	–
B116	PUPIL APP.					●				●			●		●			10'–0"	–
B117	CORRIDOR					●				●			●		●			10'–0"	–
B118	STORAGE					●				●			●		●			10'–0"	–
B119	GUIDANCE/RECEPTION					●				●			●		●			10'–0"	–
B120	CLINIC				●					●			●		●			10'–0"	–
B121	OFFICE				●					●			●		●			10'–0"	–
B122	STORAGE				●					●			●		●			10'–0"	–
B123	EXAM				●					●			●		●			10'–0"	–
B124	COT AREA				●					●			●		●			10'–0"	–
B125	SEMI–PRIVATE PLAY AREA					●				●			●		●			10'–0"	–
B125A	TOILET				●				●					●			●	10'–0"	–
B126	TEACHER'S LOUNGE/WKROOM				●					●			●		●			10'–0"	–
B127	IEP CONFERENCE					●				●			●		●			10'–0"	–
B130	CIRCULATION/READING					●				●			●		●			10'–0"	–
B131	COMPUTER ROOM					●				●			●		●			10'–0"	–
B132	TEACHER'S REFERENCE					●				●			●		●			10'–0"	–
B133	LIBRARY WORKROOM					●				●			●		●			10'–0"	–
B134	LIBRARY OFFICE					●				●			●		●			10'–0"	–
B135	CONSULT					●				●			●		●			10'–0"	–
RR–6	MEN'S RESTROOM				●				●					●		●		10'–0"	–
RR–7	WOMEN'S RESTROOM				●				●					●		●		10'–0"	–
RR–8	TOILET				●				●					●		●		10'–0"	–
RR–9	TOILET				●				●					●		●		10'–0"	–
S–3	STAIR	●								●			●			●		10'–0"	OPEN TO STAIRWELL

● MATERIAL AND FINISH APPLY TO ALL SURFACES

⊗ MATERIAL FINISH APPLIED ON SURFACE BY QUADRANT SHADED QUADRANT ORIENTATION SAME AS FLOOR PLAN

FINISH SCHEDULE – AREA "C" FIRST FLOOR

RM. NO.	ROOM NAME	FLOOR: TERRAZZO	FLOOR: SEALED CONCRETE	FLOOR: QUARRY TILE	FLOOR: CERAMIC TILE	FLOOR: VINYL COMPOSITE TILE	BASE: TERRAZZO BASE	BASE: QUARRY TILE BASE	BASE: CERAMIC TILE BASE	BASE: 4" RUBBER BASE	WALL: GYP. BD.–PAINT	WALL: C.M.U. – PAINTED	WALL: CERAMIC TILE	WALL: CMU – EPOXY FINISH	CEILING: ACOUST. LAY–IN TYPE A	CEILING: GYPSUM BD.–PAINT	CEILING: EXPOSED STRUCT.	CEILING HEIGHT	REMARKS
C100	CORRIDOR	●					●					●			●			10'–0"	–
C101	A/V STORAGE				●					●		●			●			10'–0"	–
C102	SPEECH				●					●		●			●			10'–0"	–
C103	1ST GRADE CLASSROOM				●					●		●			●			10'–0"	–
C104	1ST GRADE CLASSROOM				●					●		●			●			10'–0"	–
C105	2ND GRADE CLASSROOM				●					●		●			●			10'–0"	–
C106	2ND GRADE CLASSROOM				●					●		●			●			10'–0"	–
C107	ELEVATOR MACH. ROOM		●									●				●		–	–
C108	CORRIDOR	●					●					●			●			10'–0"	–
C109	CORRIDOR	●					●					●			●			10'–0"	–
C111	SELF CONTAINED CLASSROOM				●					●		●			●			10'–0"	–
C112	RESTROOM			●					●				●			●		10'–0"	–
C113	CHANGING				●					●		●			●			10'–0"	–
C114	LAUNDRY				●					●		●			●			10'–0"	–
C115	STORAGE				●					●		●			●			10'–0"	–
C116	CORRIDOR	●								●		●			●			10'–0"	–
C117	PRE–K CLASSROOM				●					●		●			●			10'–0"	–
C118	PRE–K CLASSROOM				●					●		●			●			10'–0"	–
C119	KINDERGARTEN CLASSROOM				●					●		●			●			10'–0"	–
C120	KINDERGARTEN CLASSROOM				●					●		●			●			10'–0"	–
C–2	CUSTODIAL		●									●				●		10'–0"	PROVIDE TA–8 AT MOP SINK, RE: SPECS
E–2	ELECTRICAL		●									●				●		–	–
M–2	MECHANICAL		●									●				●		–	–
RR–10	RESTROOM				●				●				●			●		10'–0"	–
RR–11	RESTROOM				●				●				●			●		10'–0"	–
RR–12	BOY'S RESTROOM				●				●				●			●		10'–0"	–
RR–13	GIRL'S RESTROOM				●				●				●			●		10'–0"	–
S–4	STAIR		●											●			●	10'–0"	OPEN TO STAIRWELL
S–5	STAIR		●											●			●	10'–0"	OPEN TO STAIRWELL

● MATERIAL AND FINISH APPLY TO ALL SURFACES

⊗ MATERIAL FINISH APPLIED ON SURFACE BY QUADRANT SHADED QUADRANT ORIENTATION SAME AS FLOOR PLAN

BYRON J. STEWART & ASSOC.
ARCHITECTS & PLANNERS, APC

2300 MARENGO STREET
NEW ORLEANS, LOUISIANA 70115
(504) 527-5339 (504) 527-5342 FAX

PBK
Architecture
Engineering
Planning
Facility Consulting

CARTER G. WOODSON SCHOOL
RECOVERY SCHOOL DISTRICT
2514 THIRD STREET
NEW ORLEANS, LOUISIANA

FOR CONSTRUCTION

JOB NUMBER: 8.15.128

DATE: 04/20/10

DRAWN BY:

CHECKED BY:

REVISIONS

NO.	DATE	REVISION

SHEET TITLE: FINISH SCHEDULES FIRST_FLOOR

SHEET: A-2.10