FINISH SCHEDULE – AREA "A" SECOND FLOOR

RM. NO.	ROOM NAME	FLOOR: TERRAZZO	FLOOR: SEALED CONCRETE	FLOOR: QUARRY TILE	FLOOR: CERAMIC TILE	FLOOR: VINYL COMPOSITE TILE	BASE: TERRAZZO BASE	BASE: QUARRY TILE BASE	BASE: CERAMIC TILE BASE	BASE: 4" RUBBER BASE	WALL: GYP. BD.–PAINT	WALL: C.M.U. – PAINTED	WALL: C.M.U. – EPOXY FINISH	WALL: CERAMIC TILE	WALL: CURTAIN WALL	CEILING: ACOUST.LAY–IN TYPE A	CEILING: GYPSUM BD.–PAINT	CEILING: EXPOSED STRUCT.	CEILING: PTD. EXPOSED STRUCTURE	CEILING HEIGHT	REMARKS
A200	CORRIDOR	●					●					●				●				10'–0"	–
A201	CONCESSIONS				●					●		●				●				10'–0"	–
A202	LAUNDRY				●					●		●				●				10'–0"	–
A203	AFTER SCHOOL STORAGE				●					●		●				●				10'–0"	–
A204	COACH'S OFFICE				●					●		●				●				10'–0"	–
A205	COACH'S OFFICE				●					●		●				●				10'–0"	–
A206	GIRL'S LOCKER ROOM				●				●					●					●	10'–0"	–
A207	BOY'S LOCKER ROOM				●				●					●					●	10'–0"	–
A208	PE STORAGE					●				●	●					●				10'–0"	–
A210	GYMNASIUM				●					●									●	25'–3 1/2"	TO UNDERSIDE OF STRUCTURE
C–3	CUSTODIAL	●									●							●		–	PROVIDE TA–8 AT MOP SINK, RE: SPECS
E–3	ELECTRICAL	●									●							●		–	–
M–3	MECHANICAL	●									●							●		–	–
RR–14	BOY'S RESTROOM				●				●					●				●		10'–0"	–
RR–15	GIRL'S RESTROOM				●				●					●				●		10'–0"	–
RR–16	WOMEN'S RESTROOM				●				●					●				●		10'–0"	–
RR–17	MEN'S RESTROOM				●				●					●				●		10'–0"	–
S–1	STAIR	●										●					●			–	–
S–2	STAIR	●										●					●			–	–

REMARKS: ● MATERIAL AND FINISH APPLY TO ALL SURFACES. ⊗ MATERIAL FINISH APPLIED ON SURFACE BY QUADRANT SHADED QUADRANT ORIENTATION SAME AS FLOOR PLAN

FINISH SCHEDULE – AREA "B" SECOND FLOOR

RM. NO.	ROOM NAME	FLOOR: TERRAZZO	FLOOR: SEALED CONCRETE	FLOOR: QUARRY TILE	FLOOR: CERAMIC TILE	FLOOR: VINYL COMPOSITE TILE	FLOOR: CARPET	BASE: TERRAZZO BASE	BASE: QUARRY TILE BASE	BASE: CERAMIC TILE BASE	BASE: 4" RUBBER BASE	WALL: GYP. BD.–PAINT	WALL: C.M.U. – PAINTED	WALL: CERAMIC TILE	WALL: C.M.U. – EPOXY FINISH	CEILING: ACOUST.LAY–IN TYPE A	CEILING: GYPSUM BD.–PAINT	CEILING: EXPOSED STRUCT.	CEILING HEIGHT	REMARKS
B200	BALCONY	●						●					●				●		–	–
B201	CORRIDOR	●						●					●			●			–	–
B202	TIME OUT OFFICE					●					●		●			●			–	–
E–4	ELECTRICAL		●										●					●	–	–
M–4	MECHANICAL		●										●					●	–	–
MDF–1	MDF					●					●		●			●			–	–
S–3	STAIR		●											●				●	–	–

REMARKS: ● MATERIAL AND FINISH APPLY TO ALL SURFACES. ⊗ MATERIAL FINISH APPLIED ON SURFACE BY QUADRANT SHADED QUADRANT ORIENTATION SAME AS FLOOR PLAN

FINISH SCHEDULE – AREA "C" SECOND FLOOR

RM. NO.	ROOM NAME	FLOOR: TERRAZZO	FLOOR: SEALED CONCRETE	FLOOR: QUARRY TILE	FLOOR: CERAMIC TILE	FLOOR: VINYL COMPOSITE TILE	BASE: TERRAZZO BASE	BASE: QUARRY TILE BASE	BASE: CERAMIC TILE BASE	BASE: 4" RUBBER BASE	WALL: GYP. BD.–PAINT	WALL: C.M.U. – PAINTED	WALL: CERAMIC TILE	WALL: C.M.U. – EPOXY FINISH	CEILING: ACOUST.LAY–IN TYPE A	CEILING: GYPSUM BD.–PAINT	CEILING: EXPOSED STRUCT.	CEILING HEIGHT	REMARKS
C200	CORRIDOR	●					●					●			●			VARIES	REFER SECTIONS FOR CEILING HEIGHTS
C201	TIME OUT ROOM				●					●		●			●			10'–0"	–
C202	4TH GRADE CLASSROOM				●					●		●			●			10'–0"	–
C203	4TH GRADE CLASSROOM				●					●		●			●			10'–0"	–
C204	3RD GRADE CLASSROOM				●					●		●			●			10'–0"	–
C205	3RD GRADE CLASSROOM				●					●		●			●			10'–0"	–
C206	CORRIDOR	●					●					●			●			10'–0"	–
C207	SPEECH				●					●		●			●			10'–0"	–
C208	COMPUTER LAB				●					●		●			●			10'–0"	–
C209	CORRIDOR				●					●		●			●			10'–0"	–
C211	5TH GRADE CLASSROOM				●					●		●			●			10'–0"	–
C212	5TH GRADE CLASSROOM				●					●		●			●			10'–0"	–
C213	RESOURCE ROOM				●					●		●			●			10'–0"	–
C214	TEACHER WORKROOM				●					●		●			●			10'–0"	–
C215	SCIENCE LAB				●					●		●			●			10'–0"	–
C216	PREP ROOM				●					●		●			●			10'–0"	–
C217	CORRIDOR	●						●				●			●			10'–0"	–
C–4	CUSTODIAL		●									●					●	–	PROVIDE TA–8 AT MOP SINK, RE: SPECS
E–5	ELECTRICAL		●									●					●	–	–
IDF–2	IDF			●						●		●			●			10'–0"	–
M–5	MECHANICAL		●									●					●	–	–
RR–18	BOY'S RESTROOM			●					●					●				10'–0"	–
RR–19	GIRL'S RESTROOM			●					●					●				10'–0"	–
RR–20	STAFF RESTROOM			●					●					●				10'–0"	–
S–4	STAIR		●							●							●	–	–
S–5	STAIR		●							●							●	–	–

REMARKS: ● MATERIAL AND FINISH APPLY TO ALL SURFACES. ⊗ MATERIAL FINISH APPLIED ON SURFACE BY QUADRANT SHADED QUADRANT ORIENTATION SAME AS FLOOR PLAN

FINISH SCHEDULE – AREA "C" THIRD FLOOR

RM. NO.	ROOM NAME	FLOOR: TERRAZZO	FLOOR: SEALED CONCRETE	FLOOR: QUARRY TILE	FLOOR: CERAMIC TILE	FLOOR: VINYL COMPOSITE TILE	FLOOR: CARPET	BASE: TERRAZZO BASE	BASE: QUARRY TILE BASE	BASE: CERAMIC TILE BASE	BASE: 4" RUBBER BASE	WALL: GYP. BD.–PAINT	WALL: C.M.U. – PAINTED	WALL: CERAMIC TILE	WALL: C.M.U. – EPOXY FINISH	CEILING: ACOUST.LAY–IN TYPE A	CEILING: GYPSUM BD.–PAINT	CEILING: EXPOSED STRUCT.	CEILING HEIGHT	REMARKS
C300	CORRIDOR	●						●					●				●		10'–0"	–
C301	ASSIST. PRINCIPAL'S OFFICE						●						●				●		10'–0"	–
C302	7TH GRADE CLASSROOM				●						●		●				●		10'–0"	–
C303	7TH GRADE CLASSROOM				●						●		●				●		10'–0"	–
C304	6TH GRADE CLASSROOM				●						●		●				●		10'–0"	–
C305	6TH GRADE CLASSROOM				●						●		●				●		10'–0"	–
C306	CORRIDOR				●						●		●				●		10'–0"	–
C307	CORRIDOR				●						●		●				●		10'–0"	–
C308	COMPUTER LAB				●						●		●				●		10'–0"	–
C311	8TH GRADE CLASSROOM				●						●		●				●		10'–0"	–
C312	8TH GRADE CLASSROOM				●						●		●				●		10'–0"	–
C313	SPEECH				●						●		●				●		10'–0"	–
C314	TEACHER'S CENTER/WORKROOM				●						●		●				●		10'–0"	–
C315	RESOURCE/CLASSROOM				●						●		●				●		10'–0"	–
C316	SCIENCE LAB				●						●		●				●		10'–0"	–
C317	PREP ROOM				●						●		●				●		10'–0"	–
C–5	CUSTODIAL		●										●					●	–	PROVIDE TA–8 AT MOP SINK, RE: SPECS
E–6	ELECTRICAL		●										●					●	–	–
IDF–3	IDF					●					●		●				●		10'–0"	–
M–6	MECHANICAL		●										●					●	–	–
RR–21	BOY'S RESTROOM			●					●					●				●	10'–0"	–
RR–22	GIRL'S RESTROOM			●					●					●				●	10'–0"	–
RR–23	STAFF RESTROOM			●					●					●				●	10'–0"	–
S–4	STAIR		●												●			●	–	–
S–5	STAIR		●												●			●	–	–

REMARKS: ● MATERIAL AND FINISH APPLY TO ALL SURFACES. ⊗ MATERIAL FINISH APPLIED ON SURFACE BY QUADRANT SHADED QUADRANT ORIENTATION SAME AS FLOOR PLAN

BYRON J. STEWART & ASSOC.
ARCHITECTS & PLANNERS, APC
2300 MARENGO STREET
NEW ORLEANS, LOUISIANA 70115
(504) 527-5339 (504) 527-5342 FAX

PBK
Architecture
Engineering
Planning
Facility Consulting

CARTER G. WOODSON SCHOOL
RECOVERY SCHOOL DISTRICT
2514 THIRD STREET
NEW ORLEANS, LOUISIANA

FOR CONSTRUCTION

JOB NUMBER: 8.15 128

DATE: 04/20/10

DRAWN BY:

CHECKED BY:

REVISIONS

NO.	DATE	REVISION

SHEET TITLE: FINISH SCHEDULES SECOND AND THIRD FLOORS

SHEET: A-2.11