MATCHLINE
SEE SHEET C1.0

MATCHLINE
SEE SHEET C1.0

THIS REVISED SHEET C1.1 IS ATTACHMENT #22 TO ADDENDUM #1

CONCRETE DRIVE AND PARKING AREAS NOT IN CONTRACT (TYP.)

CONCRETE CURB, PARKING AREA, PEDESTRIAN WALKWAYS NOT IN CONTRACT (TYP.)

NEW FLAG POLE. SEE 20/S0.1 FOR FOUNDATION DETAILS (TYP.)

LIGHT POLE AND FIXTURE ON CONCRETE FOUNDATION. INSTALL LIGHT POLE, FIXTURE AND FOUNDATIONS AND PILINGS, AS WELL AS ASSOCIATED CONDUITS AND WIRING TO THE POLE FOR POWER AND CONTROL AS PART OF ADD ALTERNATE #1. SEE 20/S0.1 FOR FOUNDATION DETAILS (TYP.)

NEW CONCRETE CURB. SEE 3/C6.0 FOR DETAIL (TYP.)

SEE 9/C6.0 FOR CONCRETE WHEEL STOP DETAIL

SEE 7/C6.0 FOR STRIPING DETAIL

NEW CONCRETE PAVING. SEE C5.0 AND 3/C6.0 FOR DETAILS.

DETECTABLE WARNING SURFACE. SEE 4/C6.0 FOR DETAILS.

CANOPY OVERHEAD. SEE ARCHITECTURAL PLANS FOR DETAILS (TYP.)

NEW CONCRETE DEPRESSED CURB AND SIDEWALK (TYP.)

EDGE OF STRUCTURAL SLAB (TYP.)

NEW CONCRETE SIDEWALK.

MAIN ENTRY LOBBY

LOBBY
F.F.E. = 2.97

WALL OUTLINE ABOVE (TYP.) SEE ARCH. PLANS FOR DETAILS

COURTYARD
(OPEN TO ABOVE)

PIPE BOLLARD. SEE ARCHITECTURAL PLANS FOR DETAILS.

OUTLINE OF ROOF ABOVE. SEE ARCHITECTURAL PLANS FOR DETAILS (TYP.)

OUTLINE OF ROOF ABOVE

NEW CONCRETE PAVING. SEE C5.0 AND 3/C6.0 FOR DETAILS.

TRANSFORMER PAD. SEE 12/S2.1 FOR TRANSFORMER PAD DETAILS.

PROPOSED
F.F.E. (SECOND FLOOR)= 20.97
(NGVD DATUM)

NEW CONCRETE WALKWAY. SEE STRUCTURAL PLANS FOR DETAILS.

NEW DRINKING FOUNTAIN. SEE MEP PLANS FOR DETAILS.

NEW 4'-0" HEIGHT FENCING. SEE ARCHITECTURAL PLANS FOR DETAILS.

FENCE GATE. SEE ARCHITECTURAL PLANS FOR DETAILS

FENCED IN PLAY YARD. (PRE-K THROUGH SECOND GRADE)

PLAY AREA FOR ELEMENTARY SCHOOL STUDENTS

PRIOR TO FINAL ACCEPTANCE, THE CONTRACTOR SHALL BE RESPONSIBLE FOR GRADING AND SMOOTHING OUT ALL UNPAVED AND UNFINISHED AREAS SURROUNDING THE BUILDING TO THE SATISFACTION OF THE ARCHITECT AND OWNER

PERMANENT LOCATION OF PLAY YARD. CONTRACTOR SHALL REFER TO ARCHITECTURAL SITE PLAN A1.1 FOR LIMITS, TYPE OF MATERIAL, COVERING THICKNESS, DETAILS AND NOTES.

NEW CONCRETE SIDEWALK. (PART OF ADD ALTERNATE #1)

ADA CURB RAMP. SEE 8/C6.0 FOR DETAILS.

NEW HANDICAP ACCESSIBLE PARKING SPACE SIGN. SEE ARCHITECTURAL PLANS FOR DETAILS (TYP.)

CONCRETE WHEEL STOP. SEE 9/C6.0 FOR DETAIL (TYP.)

NEW HANDICAPPED PARKING SPACE

LIGHT POLE AND FIXTURE ON CONCRETE FOUNDATION. INSTALL LIGHT POLE, FIXTURE AND FOUNDATIONS AND PILINGS, AS WELL AS ASSOCIATED CONDUITS AND WIRING TO THE POLE FOR POWER AND CONTROL AS PART OF ADD ALTERNATE #1. SEE 20/S0.1 FOR FOUNDATION DETAILS (TYP.)

EXISTING 36 INCH OAK TREE TO REMAIN. CONTRACTOR SHALL REFER TO ARCHITECTURAL SITE PLAN A1.1 FOR TREE PROTECTION NOTES.

THIS AREA OF EXISTING PAVING MAY BE USED BY THE CONTRACTOR AS PART OF "STAGING" BUT MUST EVENTUALLY DEMOLISHED AND REMOVED BY THE CONTRACTOR AS PART OF THIS JOB.

NEW WATER TOWER AND CONCRETE PAD. SEE 5/S0.2 FOR DETAILS

CELLULAR TOWER

EXISTING MICROWAVE REPEATER STATION TOWER TO REMAIN AND PROTECTED. ALSO PROTECT ASSOCIATED SUB-SURFACE UTILITY LINES

FLOOD ZONE A1 EL +1.5

FLOOD ZONE B

DITCH

1 C1.1 BUILDING– PARTIAL SITE PLAN 1"=20'-0"

GRAPHIC SCALE
(IN FEET)
1 inch = 20 ft.

MATCHLINE
SEE SHEET C1.2

MATCHLINE
SEE SHEET C1.2

MORPHY MAKOFSKY INCORPORATED CONSULTING ENGINEERS (504)488-1317 JOB NO. 09157

REVISIONS	BY
06/22/10	SCP

CONTRACTOR MUST VERIFY AND CHECK ALL JOB DIMENSIONS, DETAILS AND SPECIFICATIONS ON SITE AND REPORT ANY ERRORS, OMISSIONS AND DISCREPANCIES BEFORE PROCEEDING

NEW-PHOENIX-PRE-K-THROUGH-12-SCHOOL

NEW-PHOENIX-PRE-K-THROUGH-12-SCHOOL
12700-HWY.-39-BRAITHWAITE,-LOUISIANA-70040
FEMA-PW-4987

ATTACHMENT NUMBER 22 TO ADDENDUM NUMBER ONE

SEAL: STATE OF LOUISIANA — DONALD C. MAKOFSKY — REG. No. 18836 — REGISTERED PROFESSIONAL ENGINEER IN CIVIL ENGINEERING

04-23-10

DRAWN:	SCP
CHECKED:	SCP
SCALE:	AS NOTED
DATE:	05/21/2010

C1.1

© 2009