MATCHLINE
SEE SHEET C1.1

MATCHLINE
SEE SHEET C1.1

THIS REVISED SHEET C1.2 IS ATTACHMENT #23 TO ADDENDUM #1

EXISTING MAINTENANCE BUILDING AND CONCRETE PAD TO REMAIN.

THE CONTRACTOR SHALL CAREFULLY DISMANTLE THE EXISTING BASEBALL FIELD SCOREBOARD, BASEBALL BLEACHERS AND BASEBALL FIELD FENCING. THE CONTRACTOR SHALL TAKE A PORTION OF BASEBALL FIELD FENCING AND CREATE A STORAGE YARD BY INSTALLING THIS FENCING (WITH A 12' MINIMUM WIDE PAIR-OF-GATES OPENING) USING THE TYPICAL FENCING DETAILS FOUND ON SHEET A1.2 IN FRONT OF THIS EXISTING MAINTENANCE BUILDING. THE REMAINDER OF THE BASEBALL FENCING, THE BASEBALL BLEACHERS AND SCOREBOARD ARE TO BE STORED IN THIS YARD BY THE CONTRACTOR IN A MANNER THAT PROTECTS THEM FROM THE WEATHER.

THIS AREA OF CONTRACTOR SITE ACCESSWAY IS TO BE GRADED AND IS TO BE AUGMENTED BY ADDITIONAL LOADS OF RUBBLE OR GRAVEL AS NEEDED TO MAKE A VIABLE SITE ACCESS ROAD FOR THE CONTRACTOR WHEN CONDITIONS ARE WET.

SECTION OF RELOCATED FENCE AS DESCRIBED BELOW

SECTION OF NEW CHAINLINK FENCE. CONTRACTOR SHALL MAKE SURE TO MATCH THE NEW SECTION OF CHAINLINK FENCE WITH THE EXISTING CHAINLINK FENCE. SEE ARCHITECTURAL PLANS FOR NOTES AND DETAILS.

EXISTING FENCE GATE SHALL REMAIN IN PLACE.

EXISTING FENCE SHALL BE RELOCATED NORTHWARD IN LINE WITH EXISTING FENCE. CONTRACTOR SHALL REINSTALL THE FENCE PER FENCE DETAILS ON SHEET A1.2.

EXISTING RUBBLE ROAD. CONTRACTOR SHALL USE THIS ROAD FOR ACCESS TO AND FROM THE CONSTRUCTION SITE. "NO" OTHER ROADS OR PAVED AREAS WITHIN THE SITE OF SCHOOL BUILDING SHALL BE USED BY THE CONTRACTOR FOR SITE ACCESS.

EXISTING TEMPORARY CLASSROOM TRAILERS AND GYMNASIUM NOT TO BE DISTURBED DURING CONSTRUCTION

EXISTING FENCE

1 STORY BRICK

FF = 2.7

ASPHALT

GREASE TRAP

GRASS

18 IN OAK

APPROXIMATE LOCATION OF SHELL WALK

RECENT DEMOLITION OF EXISTING BUILDING IN THIS AREA

SEE DETAIL A

DITCH

GAS METER

CONC

SWALE

12" CULVERT (TYP)

CONCRETE WALK

CONC PAD

CONC RAMP

1 STORY BRICK PORTABLE BLDG

1 STORY METAL PORTABLE BLDG

1 STORY METAL PORTABLE

MATCHLINE
SEE SHEET C1.3

MATCHLINE
SEE SHEET C1.3

1 C1.2 BUILDING– PARTIAL SITE PLAN 1"=20'-0"

N

GRAPHIC SCALE

20 0 10 20 40 80

(IN FEET)
1 inch = 20 ft.

MORPHY MAKOFSKY INCORPORATED
CONSULTING ENGINEERS
(504)488-1317
JOB NO. 09157

REVISIONS	BY
06/22/10	SCP

CONTRACTOR MUST VERIFY AND CHECK ALL JOB DIMENSIONS, DETAILS AND SPECIFICATIONS ON SITE AND REPORT ANY ERRORS, OMISSIONS AND DISCREPANCIES BEFORE PROCEEDING

NEW-PHOENIX-PRE-K-THROUGH-12-SCHOOL

NEW-PHOENIX-PRE-K-THROUGH-12-SCHOOL
12700-HWY.-39-BRAITHWAITE,-LOUISIANA-70040
FEMA-PW-4987

ATTACHMENT NUMBER 23 TO ADDENDUM NUMBER ONE

SEAL
STATE OF LOUISIANA
DONALD C. MAKOFSKY
REGISTERED PROFESSIONAL ENGINEER IN CIVIL ENGINEERING
06/04/2010

04-23-10

DRAWN:	SCP
CHECKED:	SCP
SCALE:	AS NOTED
DATE:	05/21/2010

C1.2

© 2009