MATCHLINE
SEE SHEET C1.2

MATCHLINE
SEE SHEET C1.2

THIS REVISED SHEET C1.3 IS ATTACHMENT #24 TO ADDENDUM #1

EXISTING FENCE GATE SHALL REMAIN IN PLACE.

EXISTING FENCE SHALL BE RELOCATED NORTHWARD IN LINE WITH EXISTING FENCE. CONTRACTOR SHALL REINSTALL THE FENCE PER FENCE DETAILS ON SHEET A1.2.

EXISTING RUBBLE ROAD. CONTRACTOR SHALL USE THIS ROAD FOR ACCESS TO AND FROM THE CONSTRUCTION SITE.
"NO" OTHER ROADS OR PAVED AREAS WITHIN THE SITE OF SCHOOL BUILDING SHALL BE USED BY THE CONTRACTOR FOR SITE ACCESS.

EXISTING TEMPORARY CLASSROOM TRAILERS AND GYMNASIUM NOT TO BE DISTURBED DURING CONSTRUCTION.

EXISTING FENCE

TEMPORARY LOCATION OF PLAY YARD. CONTRACTOR SHALL REFER TO ARCHITECTURAL SITE PLAN A1.1 FOR LIMITS, TYPE OF MATERIAL, COVERING THICKNESS, DETAILS AND NOTES.

TEMPORARY LOCATION OF PLAY YARD. CONTRACTOR SHALL REFER TO ARCHITECTURAL SITE PLAN A1.1 FOR LIMITS, TYPE OF MATERIAL, COVERING THICKNESS, DETAILS AND NOTES.

TEMPORARY SIGN: SEE ARCHITECTURAL SITE PLAN A1.1 FOR NOTES AND DETAILS.

PHOENIX EDUCATIONAL ASSOCIATION

1 STORY VINYL BLDG ON SLAB

1 STORY METAL PORTABLE BLDG

1 STORY BRICK PORTABLE BLDG

LOT P-1

1 STORY FIRE STATION

SEWER LIFT STA.

LA. HIGHWAY 15

MISSISSIPPI RIVER

Down River

1 C1.3 BUILDING– PARTIAL SITE PLAN 1"=20'-0"

GRAPHIC SCALE
(IN FEET)
1 inch = 20 ft.

MORPHY MAKOFSKY INCORPORATED CONSULTING ENGINEERS (504)488-1317 JOB NO. 09157

REVISIONS	BY
06/22/10	SCP

CONTRACTOR MUST VERIFY AND CHECK ALL JOB DIMENSIONS, DETAILS AND SPECIFICATIONS ON SITE AND REPORT ANY ERRORS, OMISSIONS AND DISCREPANCIES BEFORE PROCEEDING

NEW-PHOENIX-PRE-K-THROUGH-12-SCHOOL
NEW-PHOENIX-PRE-K-THROUGH-12-SCHOOL
12700-HWY.-39-BRAITHWAITE,-LOUISIANA-70040
FEMA-PW-4987

ATTACHMENT NUMBER 24 TO ADDENDUM NUMBER ONE

SEAL
STATE OF LOUISIANA
DONALD C. MAKOFSKY
REG. No. 18436
REGISTERED PROFESSIONAL ENGINEER IN CIVIL ENGINEERING
04-23-10

DRAWN:	SCP
CHECKED:	SCP
SCALE:	AS NOTED
DATE:	05/21/2010

C1.3

© 2009