

ADDENDUM NO. 5:**Banner Chevrolet**

February 21, 2005

ROZAS - WARD / A.I.A. ARCHITECTS1010 Common Street, Suite 2750
New Orleans, Louisiana 70112**Banner Chevrolet - Parts Storage Building**5950 Chef Mentuer Hwy.
New Orleans, LA 70126

The Construction Documents for the above referenced project have been modified, corrected and/or supplemented by this Addendum No.5 as listed below:

ARCHITECTURAL:

1. CLARIFICATION: Provide \$250.00/leaf allowance for door hardware.
2. CLARIFICATION: Ceramic tile (where occurring) can be thin set.
3. CLARIFICATION: Alternate No.1 - Roof and wall panels shall be mfrs. standard.
4. CLARIFICATION: Alternate No.1 - Wall panels shall be pre-finished 26 GA. "R" panel with 20 year warranty on coating.
5. CLARIFICATION: Alternate No.1 - Roof fasteners shall be SDS panel to panel and panel to structural.
6. CLARIFICATION: Alternate No.1 - Wall insulation shall be 3" vinyl faced insulation with a vinyl facing, PSK light duty.
7. CLARIFICATION: Alternate No.1 - Roof panels shall be 26 GA. "R" panel with a white coating.
8. CLARIFICATION: Alternate No.1 - Roof fasteners shall be SDS panel to panel and panel to structural.
9. CLARIFICATION: Alternate No.1 - Roof insulation shall be 3" vinyl faced insulation with a vinyl facing, PSK light duty.
10. CLARIFICATION: Include embed plates at the following locations:
 - At side wall for attaching the concrete panels at the wind beam
 - At the skewed endwall to support load bearing angle to support purlins
 - Concrete panels at the endwalls will connect to a rake channel or to the ridged frame and angle welded to the embed plate and to the ridged frame
11. CLARIFICATION: Elevations, Sheet A4.1 - Skewed endwall shall have a gutter with counter flashing, weather sealed.
12. CLARIFICATION: Exterior of concrete panels shall be painted per the following:
 - 1 ct. Sherwin Williams Loxon Block Surfacers (A24W200)
 - 2 cts. Sherwin Williams ConPlex XI. Smooth Elastomeric High Build Coating A5-400 Series

END OF ADDENDUM NO. 5